

Oropi Reservoir



Main Contractor: Fulton Hogan Northern Civil

Sub Contractor: Preco Construction (Prestressed Panels)

Supplier: Supacrete Concrete

Date: May 2005

This 5500000 litre reservoir is the second main water storage for the supply to the Tauranga area. Pre stressed panels were constructed on site. Concrete's supplied included low water/ cement ratio 40MPa super plasticized concrete and self compacting concrete for the in fills. X m3 concrete was supplied over months